

## Portable Cabin

**Interline portable cabins** are specially custom designed and build for usage such as site office, storage facilities, classrooms, conference rooms, dining hall, commercial kitchens, single and multiple accommodation, temporary and permanent housing facilities. All units are built with forklift handling and/or lifting eyes for crane handling. Units are specially design for transportation by either a 20ft or 40ft standard platform trailers. Portable cabins can be as single, grouped or interconnecting units. They can also be supplied with 'second' roofs to present a permanent and aesthetically pleasing appearance. Size is only limited by transport limitations and various countries' building code regulations.

### DIMENSION

Units are available from the smallest required size units 12m long x 3m wide x3m high (40'x10'x10'). Size is only limited by site and transport limitation and regulations.

### STRUCTURE

**Base Skid-** Mild steel structural section frames incorporating a pair of forkliftpockets. Galvanised steel stud floor joists set out to suit flooring materials.

**Framework-** Steel stud frames and incorporating square hollow sectionswhere required by design. (Walls and roof)

### FLOORING

Generally 18mm thk. WBP ply to dry areas and finished with vinyl tiles or as client specified. Wet area floors employ a cement board base finished with ceramic floor tiles.

### DOORS

Doors can be located at almost any position around the perimeter type, with quantity and size tocustomer requirements. External doors are generally metal framed and clad. Timber and aluminum types are available. Internal doors are generally aPVC door and frame. Doors are hung on stainless steel hinges and provided with a lockset.

### WINDOWS

Windows can be located at almost any position around the perimeter to clients requirements. Generally windows are natural anodized aluminum framed double sliding type with tinted glass. Alternatives are availabl upon request including optional security screens.

### LININGS

Roof : INTERDEK or HI-RIB Colourstrong depending upon client requirements.

External Walls : INTERDEK Colourstrong cladding laid horizontally and flashed at roof, corners and any wall penetration.

Internal Walls :Dry area - linings can be WBP ply, PVC faced ply or gypsum.

Ceilings : Dry area- as for walls. Wet area-PVC T&G board or cement board.



### INSULATION

Units have roof and external walls lined with 50mm fibre-glass insulation or as client specifies.

### ELECTRICAL

All units are provided with a suitably sized main circuit breaker and weatherproof outlet socket for incoming power. The electrical installation of each unit is provided in accordance with customer requirements.

### AIR CONDITIONING

Portable Cabin units can be supplied with framed air -conditioning window unit openings. Alternatively units can be supplied and installed( split or window types)

### LIFTING

All units are provided with both a pair of forklift pockets and number four number fixed or removable top lifting eyes for forklift or craine hoisting.

### OPTIONS:

- \*On site insstallation including precast RC Foundations.
- \*Second Roofs
- \*Internal Partitions.
- \*Plumbing including water and sanitary piping and fixtures.
- \*Built in Cabinets and Furnishings.
- \*End gutters.
- \*Other client specified requirements

**Interline (B) Sdn Bhd.**

Lot 56, 57, 58 & 59 Beribi Industrial Complex II BE 1118 Gadong, P.O. Box 520 Postal Code BE 3978 Bandar Seri Begawan - Brunei Darussalam

Telp (673) 2448721-24 Fax (673) 2448725 / (673) 8227788 - Whatsapp Only - Email : info@interline-asia.com